



ELEVATION, SIDE 6



SECTION A-A, SIDE 4



SECTION B-B, SIDE 5

D C B A	FOR APPROVAL EXPOSURE CLASS ADJUSTED EXPOSURE CLASS, AND CONCRETE STRENGTH FOR WALL PANEL ADJUSTED FIRST ISSUE				LK LLC LK LLC	2026.01.08 2025.11.14 2025.11.04 2025.10.07			
	REV.:		DESCRIPTION:		INIT.:		DATE:		
	CAST IN PARTS				CONCRETE DETAILS:		SIDE	SURFACE	EXP.CLASS
	MARK	SIDE	NO.	DESCRIPTION, DETAILS	CONCRETE:		①	Steel Form	XC4, XF2, DC-4z
A	-	-	-	EXPOSURE CLASS:		DC4, XF4, XC3/4	②	Steel Form	XC4, XF2, DC-4Z
B	6	4	STARCON LIFTING EYES 5T-95	RECEPT:		-	③	Steel Form	XC4, XF2, DC-4Z
C	6	1	SSRCP1675 (CERTEX)	KONTROLKLASSE(DK):		-	④	Steel Form	XC4, XF2, DC-4Z
D	3	3	NAILING BLOCK Ø21/25x25mm	WALL PANEL WEIGHT:		3352 Kg	⑤	Steel Form	XC4, XF2, DC-4Z
E	3-4	10	PVC-DUCT Ø23/25mm	TOLERANCES:		According to A-Consult Quality Manual	⑥	Steel Float Form	XC4, XF2, DC-4Z
F	-	-	-	DETAIL DRAWING:		-	HOLE	Steel Form	XC4, XF2, DC-4Z
G	-	-	-	GENERAL NOTES:			RECESS	Steel Form	XC4, XF2, DC-4Z
H	-	-	-	ALL DIMENSIONS IN MILLIMETRES. NO DIMENSIONS ARE TO BE SCALED FROM THE DRAWING. THE POST DRILLING OF PRECAST PANELS FOR PIPE CONNECTIONS OR BOLT FIXING IS PERMITTED, HOWEVER THIS WORK MUST BE CARRIED OUT WITH SPECIAL ATTENTION BEING PAID TO THE LOCATION OF THE POST TENSIONING TENDONS WITHIN THE STRUCTURE, ENSURING THAT THE OUTER DIAMETER OF ANY HOLE/APERTURE IS NO LESS 75 MM AWAY FROM THE OUTER DIAMETER OF ANY HOLE/APERTURE IS NO LESS 75 MM AWAY FROM THE OUTER DIAMETER OF ANY POST TENSIONING TENDONS. TENDON LOCATION TO BE MEASURED FROM TOP OF WALL DRAWING FOR LOCATION PLEASE REFER TO "AS BUILT" DRAWINGS AND ANCHOR LOCATION IN BUTTRESS(ES) FURTHER GUIDANCE CAN BE SOUGHT FROM A-CONSULT.					
I	-	-	-						
J	-	-	-						
K	-	-	-						
L	-	-	-	REMARKS:					
M	-	-	-						
Client info:									
MWHT									
-									
-									
Date Plotted:	2026.01.08		Made by:	LK	Check by:	SGK	Scale:	NTS	
Project no.:	430773		Project name:	Knapp Mill			STATUS FOR APPROVAL		
Constuction place address:									
Description:					Drg.no.:	Issue:			
CONCRETE LAYOUT					AQ430773-00-45-32-1100 D				
WALL PANEL - STANDARD									
TANK TYPE: N4500-32-2B/2									
A-CONSULT Ltd. The Barn Manor Business Park East Drayton					Tel.: +44(0)1777249444 Fax: +44(0)1777248452 e-mail: info@aconsult.co.uk http://www.aconsult.co.uk				